BRUHATH BANGALORE MAHANAGARA PALIKE,
DASARAHALLI ZONE
Office of the Executive Engineer Dasarahalli Division

Schedule-B

BBMP/EE/DD/Ten/12(2)/2019-20

NAME OF WORK: Improvements and maintenance of Culverts at Muneshwara Block, Vijayalakshmi Layout and Surrounding Area in ward no 13 Shettyhalli Sub Division.(Call-2)

Sl. No	Description of work	Unit	Qty	Rate quoted by the Contractor Smt.K MANJULA ( )	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means for roads, drains & similar works in ordinary soil invoiving , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per specification	Cum	92.00	203.45	Rupees Two Hundred Three and Forty Four Paise Only
2	Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications.	Cum	13.80	5313.46	Rupees Five Thousand Three Hundred Thirteen and Forty Six Paise Only
3	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No. 1500, 1700, 2200. including cost of materials, labour, HOM complete as per specificationsdo- Wall & bottom thickness 15cm	Cum	55.66	6928.80	Rupees Six Thousand Nine Hundred Twenty Eight and Seventy Nine Paise Only
4	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specifications.	Tonne	5.01	70880.44	Rupees Seventy Thousand Eight Hundred Eighty and Forty Four Paise Only

Signature of the Contractor

Executive Engineer
Dasarahalli Division.

EXECUTIVE ENGINEER
Bruhat Bengaluru Mahanagara Palike
Dasarahalli Division, Bengaluru-73.

Signature of the Contractor,

Executive Engineer,
Dasarahalli Division